Form C-10
Rev. 06-06-18

COMMONWEALTH OF VIRGINIA
DEPARTMENT OF TRANSPORTATION
CHANGE ORDER FORM

Contract ID No.: 25038 FHWA No.: TAP-5111(520) State Project No.: EN20-809,C501

Original Contract Value: $949,402.00 Total of Other Change Orders: $2,000.00 Change Order Number: 002

NOTE: If additional space is needed, use additional Supplemental Attachment sheet(s).

II. Change Category: PLAN

I. Responsible Charge Engineer's Explanation of Entitlement with Detailed Description and Location of Proposed Work:

Plan Sheet 7(2) requires removal of an existing 8" valve at the Foxwood Drive entrance. Plans depict that the existing 8" water line 90's off of the valve downstation. However, there is a tee that allows for the existing 8" water line to also continue upstation. This was not captured in project plans. It can't be confirmed that the water line continuing is active. Stafford County Water Authority has authorized a water shut off allowing for the contractor to cut and cap the existing water line and remove approximately 60.00 LF. Removal will allow for installation of the planned 8" waterline. No time extension will be given.

III. Entitlement Conditions: ☐Changes in Character of Work ☐Value Engineering Proposal ☒Differing Site Condition

IV. Extension of Time: Fixed Completion Date for this contract prior to approval of this Work Order: 4/30/2026

Fixed Completion Date for this contract upon approval of this Work Order: 4/30/2026

Item Code	Spec. No.	Item Description	Quantity	Unit	Unit Price	Increase	Decrease
N/A	520	Cut and cap existing water line; remove approximately 60.00 LF of existing water line	1.0	LS	$18,200.00	$18,200.00	
			Net Increase/Decrease:			$18,200.00	
			Net Total:			$18,200.00	

Federal Funding: ☒Participating ☐Non-Participating

Funding Source/Charge:_____

I/We hearby agree to perform and/or non-perform as indicated, the work described herein and at the unit prices set forth and that such work shall be performed in accordance with the contract provisions and specifications and/or other provisions incorporated herein. I/We and VDOT agree that this Change Order fully resolves and settles all claims, demands, or damages of any kind relating to or arising out of the work set forth in this Change Order, including but not limited to delay, impact, and acceleration.

Contractor M&F Concrete, Inc by Benjamin Harvey (Officer or Print Name)
(Name of Firm)

Digitally signed by Benjamin Harvey
DN: C=US, E=ben@mfbuild.com, O=M&F Contractor Administrator/P.M., CN=Benjamin Harvey
Reason: I am approving this document
Date: 2026.02.03 14:15:14-05'00'

☐ Unilateral Change Order

(Signature) (Date)

Locality Approval:

James Morrison Project Manager James E. Morrison Jr. Digitally signed by James E. Morrison Jr. Date: 2026.02.02 09:06:27 -05'00' 02/02/2026

(Print Name) (Title) (Signature) (Date)

FHWA Approval (If Required):

(Print Name)

VDOT Approval*:

(Signature) (Date)

(Print Name) (Title) (Signature) (Date)

* See Contract Change Management IIM for Process and Authorities.